



### **ADDENDUM No. #3**

Project Name: WATER MAIN EXTENSION  
RFP NO. PW2021-36  
Date: May 3, 2021  
Sent: Fax/E-mail/webpage

This addendum submission is issued to clarify, supplement and/or modify the previously issued Solicitation, and is hereby made part of the Documents. All requirements of the Documents not modified herein shall remain in full force and effect as originally set forth. It shall be the sole responsibility of the bidder to secure Addendums that may be issued for a specific solicitation.

#### **QUESTION #1**

After looking through the bid items a particular thing caught our attention. There are two bid items that address the pipe installations including the excavation by linear footage. (please, look for bid item **16" DIP water (including excavation)** and **8" DIP water (including excavation)**) but there are also two bid items for the excavations (please, look for bid items **Regular Excavation for 8" pipe (3' wide trench cut)** and **Regular Excavation for 16" pipe (3.5' wide trench cut)**).

If we analyze the cubic yards quantities on the excavation bid items based on the requested trench width it matches the linear footage described in the DIP pipe installation bid items. As you may understand, this causes confusion and that's why I kindly request for you to provide a clarification.

#### **RESPONSE:**

Attached to Addendum No. 3 is a revised Schedule of Values form, (**Exhibit I, Scope of Services, Attachment D.**) Line Items #1 & #2 of the Schedule of Values for the 16" and 8" have been revised from: **removing the "including excavation to "including furnishing, delivery and installation."**

**The Revised Schedule Values from, (Exhibit I, Scope of Services, Attachment D,) shall replace the Schedule of Values form provided in the RFP and shall be a part of the RFP by way of reference.**

**IT SHALL BE THE SOLE RESPONSIBILITY OF THE BIDDER TO SECURE ADDENDUMS THAT MAY BE ISSUED FOR A SPECIFIC SOLICITATION.**

ADDENDUM No. 3  
May 3, 2021



**CITY OF SOUTH MIAMI**  
**WATER MAINS**



**ATTACHMENT D - "SCHEDULE OF VALUES"**

ITEM NO.	ITEM DESCRIPTION	UNIT	EST. QTY	UNIT COST	TOTAL COST
1	16" D.I.P. Water (including furnishing, delivery and installation)	L.F.	661		
2	8" D.I.P. Water (including furnishing, delivery and installation)	L.F.	1554		
3	36" x 16" Tapping Sleeve (w/ 16" Tap. Valve)	EA.	1		
4	16" x 8" Tapping Sleeve (w/ 8" Tap. Valve)	EA.	1		
5	16" x 16" Tee (w/ Rest.)	EA.	1		
6	16" x 8" Reducer	EA.	1		
7	8" x 8" Tapping Sleeve (w/ 8" Tap. Valve)	EA.	1		
8	8" x 6" Tee w/ Rest.	EA.	2		
9	16" Gate Valve	EA.	1		
10	8" Gate Valve	EA.	3		
11	6" Gate Valve	EA.	2		
12	16" Plug	EA.	1		
13	8" Plug	EA.	4		
14	16"-45° Bend (w/ Rest.)	EA.	1		
15	8"-45° Bend (w/ Rest.)	EA.	7		
16	2" Flushing Valve Outlet	EA.	2		
17	Air Release Valve	EA.	4		
18	Fire Hydrant Assembly (with bollards & concrete pad)	EA.	2		
19	1" Water Service	EA.	11		
20	5/8" Single Meter	EA.	7		
21	2-5/8" Dual Meter	EA.	4		
22	1" Corp. Stop	EA.	6		
23	2" Style Dresser Boltless Coupling	EA.	4		
24	2" Comp. Fitting Ball Valve (w/ No. 2 Valve Box & Lid)	EA.	2		
25	1-1/2" x 2" Corp. Stop	EA.	2		
26	2"-90° Bend	EA.	2		
27	2" x 2" Tee	EA.	2		
<b><i>SUBTOTAL</i></b>					
1	Regular Excavation for 8" Pipe (3' Wide Trench Cut)	C.Y.	938		
2	Regular Excavation for 16" Pipe (3.5' Wide Trench Cut)	C.Y.	512		
3	Milling & Resurfacing of Exist. Pavmt. (1" Thick, "FC-9.5")	S.Y.	3633		
4	Pavement Restoration Type "I", "FC-9.5" Asphaltic Concrete (1" thick)	S.Y.	888		
5	Pavement Restoration Type "I", "SP-9.5" Asphaltic Concrete (1" thick)	S.Y.	888		
6	Pavement Restoration Type "I", Limerock Base (8" Thick) Double Course Primed	S.Y.	888		
7	Milling & Resurfacing of Exist. Pavmt. (1-1/2" Thick, "FC-9.5") (On FDOT Roads)	S.Y.	2203		
8	Pavement Restoration Type "II", "FC-9.5" Asphaltic Concrete (1" thick) (On FDOT Roads)	S.Y.	530		
9	Pavement Restoration Type "II", "SP-12.5" Asphaltic Concrete (2-1/2" thick) (On FDOT Roads)	S.Y.	530		
10	Pavement Restoration Type "II", Limerock Base (On FDOT Roads)	S.Y.	530		
11	Concrete Curb and Gutter (Type "D")	L.F.	3		
12	Concrete Curb and Gutter (Type "F")	L.F.	6		
13	4" Thick Concrete Sidewalk	S.Y.	25		
14	Sodding (includes watering)	S.Y.	145		
15	Driveway Restoration (Paver)	S.Y.	19		
<b><i>SUBTOTAL</i></b>					
1	Retro-Reflective Pavement Marker (Yellow/Yellow)	EA.	169		
2	Retro-Reflective Pavement Marker (White/Red)	EA.	20		
3	Directional Arrows (Thermoplastic)	EA.	2		
4	Solid Traffic Stripe (6" Double Yellow) (Thermoplastic)	L.F.	412		
5	Skip Traffic Stripe (6" White) (Skip 2-4) (Thermoplastic)	L.F.	43		
6	Skip Traffic Stripe (6" White) (Skip 10-30) (Thermoplastic)	L.F.	750		



**CITY OF SOUTH MIAMI**  
**WATER MAINS**



**ATTACHMENT D - "SCHEDULE OF VALUES"**

ITEM NO.	ITEM DESCRIPTION	UNIT	EST. QTY	UNIT COST	TOTAL COST
7	Solid Traffic Stripe (6" White) (Thermoplastic)	L.F.	897		
8	Solid Traffic Stripe (6" Yellow) (Thermoplastic)	L.F.	817		
9	Solid Traffic Stripe (8" White) (Thermoplastic)	L.F.	27		
10	Solid Traffic Stripe (12" White) (Thermoplastic)	L.F.	297		
11	Solid Traffic Stripe (18" Yellow @ 45°) (Thermoplastic)	L.F.	26		
12	Solid Traffic Stripe (24" White) (Thermoplastic)	L.F.	144		
13	Yield Line (Five 18"x27" White Triangles) (Thermoplastic)	EA.	3		
<b><i>SUBTOTAL</i></b>					
	Uniformed, off-duty police officers for the purpose of maintenance of traffic	HR	960	\$52	\$49,920.00
	Mobilization and Demobilization, Bond, Insurane and MOT (10% of Subtotal)	L.S.	1		
	Contingency allowance for unseen conditions, minor construction changes & quantity adjustments (10% of Subtotal)	L.S.	1		
	Permits, fees, and inspections (3% of Construction Total)	L.S.	1		
<b><i>TOTAL PROJECT</i></b>					